



NOT TO SCALE

NOTES:

1. TOP 12" OF SUBGRADE TO BE MIXED IN PLACE AND COMPACTED TO 95% STANDARD PROCTOR.
2. THE CONTRACTOR WILL PROVIDE COMPACTION TEST RESULTS AND SOIL ANALYSIS TEST RESULTS FROM AN APPROVED TESTING LABORATORY. LOCATION OF TESTS SHALL BE DETERMINED BY THE CITY ENGINEER OR THEIR REPRESENTATIVE, BUT ARE NOT TO EXCEED ONE PER 250' OF TRAIL BED.
3. FULL WIDTH OF R/W TO BE CLEARED, GRUBBED, AND GRADED WITH SLOPE NOT TO EXCEED 1/2" PER FOOT UNLESS DIRECTED OTHERWISE BY THE CITY ENGINEER.
4. ALL EXPOSED EARTH SURFACES TO BE GRASSED.

TYPICAL ASPHALT  
TRAIL SECTION

7.14

DATE	BY	DESCRIPTION
9/30/05	CKC	CREATED DETAIL
6/21/23	BGM	CHANGE FONT, TITLE BLOCK

